

ABBREVIATIONS	
AB	ANCHOR BOLT
ABV	ABOVE
ADJ	ADJACENT
AFF	ABOVE FINISH FLOOR
AGGR	AGGREGATE
ALT	ALTERNATE
ALUM	ALUMINUM
APPROX	APPROXIMATELY
ARCHCL	ARCHITECTURAL
BD	BOARD
BLDG	BUILDING
BLKG	BLOCKING
BM	BEAM
BN	BOUNDARY NAILING
BO	BOTTOM OF
BOVT	BOTTOM
BRG	BEARING
BTWN	BETWEEN
CAM	CAMBER
CANTL	CANTILEVERED
CTR	CENTERED
CL	CENTERLINE
CLR	CLEAR
CMU	CONC MASONRY UNIT
COL	COLUMN
CONC	CONCRETE
CONN	CONNECTION
CONST	CONSTRUCTION
CONT	CONTINUOUS
D	PENNY
D/DIA	DIAMETER
DBL	DOUBLE
DEPT	DEPARTMENT
DPL	DOUGLAS FIR LARCH
DIAG	DIAGONAL
DTL	DETAIL
DIA	DIAMETER
DIM	DIMENSION
DN	DOWN
DWG	DRAWING
DWL	DOWEL
EA	EACH
EJ	EXPANSION JOINT
ELEV	ELEVATION
ELEC	ELECTRIC
EN	EDGE NAILING
ENCLD	ENCLOSED
ENR	ENGINEER OF RECORD
EQ	EQUAL
EQUIP	EQUIPMENT
EXIST	EXISTING
EXP	EXPANSION
EXT	EXTERIOR
EXTD	EXTENDED
FD	FLOOR DRAIN
FOUND	FOUNDATION
FF	FINISH FLOOR
FG	FINISH GRADE
FIN	FINISH
FLR	FLOOR
FRMG	FRAMING
FT	FOOT OR FEET
FTG	FOOTING
FLRR	FURRING
GA	GAUGE
GLB	GLU-LAM BEAM
GRND	GROUND
GR	GIRDER TRUSS
GYP	GYPSUM WALLBOARD
HDR	HEADER
HGR	HANGER
HGT HT	HEIGHT
HORIZ	HORIZONTAL
HTR	HIP TRUSS
INSUL	INSULATION
INT	INTERIOR
JT	JOINT
LAM	LAMINATE
LAT	LATERAL
LBS	POUNDS
LSL	LAM STRAND LUMBER
LT	LIGHT
LVL	LAM VENEER LUMBER
LW	LONG WAY
MAS	MASONRY
MAX	MAXIMUM
MECH	MECHANICAL
MFR	MANUFACTURER
MFRD	MANUFACTURED
MIN	MINIMUM
MISC	MISCELLANEOUS
NO	NUMBER
N	COMMON NAIL
NTS	NOT TO SCALE
O	OVER
OC	ON CENTER
OH	OPPOSITE HAND
OPNG	OPENING
PA	POST FROM ABOVE
PL	PLATE
PLYWD	PLYWOOD
PNL	PANEL
PREFAB	PREFABRICATED
PSL	PARALLEL STRAND LUMBER
PSI	LBS PER SQ INCH
PT	POST-TENSIONED
PND	POUND
RAD	RADIUS
REF	REFERENCE
REINF	REINFORCING
REQD	REQUIRED
S	SINKER NAIL
SCHED	SCHEDULE
SF	SQUARE FEET
SECT	SECTION
SHTHG	SHEATHING
SM	SIMILAR
SPEC	SPECIFICATIONS
SQ	SQUARE
STD	STANDARD
STGD	STAGGERED
STL	STEEL
STRUCT	STRUCTURAL
SYM	SYMMETRICAL
SWL	SHEAR WALL
SPN	SOLE PLATE NAILING
SW	SHORT WAY
T&G	TONGUE AND GROOVE
T&B	TOP AND BOTTOM
THK	THICK
TO	TOP OF
TRIM	TRIMMER
TR	TRUSS
TS	TUBE STEEL
TS L&L	TIMBERSTRAND BEAM
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE
VERT	VERTICAL
W/ W/O	WITH WITHOUT
WS	WOOD SCREW
WT	WEIGHT

NOTES

GENERAL

- ALL WORK SHALL CONFORM TO THE MINIMUM STANDARDS OF THE FOLLOWING CODE: THE INTERNATIONAL BUILDING CODE, 2018 EDITION, OTHER REGULATING AGENCIES WHICH HAVE AUTHORITY OVER ANY PORTION OF THE WORK, AND THOSE CODES AND STANDARDS LISTED IN THESE NOTES AND SPECIFICATIONS.
- THE STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, SHORING, FLOOR LOADS DUE TO CONSTRUCTION EQUIPMENT, ETC. OBSERVATION VISITS TO THE SITE BY THE STRUCTURAL ENGINEER SHALL NOT INCLUDE INSPECTIONS OF THE ABOVE ITEMS.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO STARTING CONSTRUCTION. THE ARCHITECT SHALL BE NOTIFIED OF ANY DISCREPANCIES OR INCONSISTENCIES.
- DIMENSIONS SHALL TAKE PRECEDENCE OVER THE SCALE SHOWN ON DRAWINGS.
- NOTES AND DETAILS ON PLANS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS.
- SEE ARCHITECTURAL PLANS FOR THE FOLLOWING UNO:
 - SIZE AND LOCATION OF ALL DOOR AND WINDOW OPENINGS.
 - SIZE AND LOCATION OF ALL INTERIOR AND EXTERIOR NON-BEARING PARTITIONS.
 - SIZE AND LOCATION OF ALL CONCRETE CURBS, FLOOR DRAINS, SLOPES, DEPRESSIONED AREAS, CHANGES IN LEVEL, CHAMFER, GROOVES, INSERTS, ETC.
 - SIZE AND LOCATION OF FLOOR AND ROOF OPENINGS.
 - FLOOR AND ROOF FINISHES.
 - STAIR FRAMING AND DETAILS.
 - DIMENSIONS NOT SHOWN ON STRUCTURAL PLANS.
- SEE MECHANICAL, PLUMBING, AND ELECTRICAL PLANS FOR THE FOLLOWING:
 - PIPE RUNS, SLEEVES, HANGERS, TRENCHES, WALL AND SLAB OPENINGS, ETC., (EXCEPT AS SHOWN OR NOTED).
 - ELECTRICAL, CONDUIT RUNS, BOXES, OUTLETS IN WALLS AND SLABS.
 - CONCRETE INSERTS FOR ELECTRICAL, MECHANICAL, OR PLUMBING FIXTURES.
 - SIZE AND LOCATION OF MACHINE EQUIPMENT BASES, OR ANCHOR BOLTS FOR MOUNTS.
 - SIZE AND LOCATION OF ALL MECHANICAL UNITS.
- OPENINGS, POCKETS, ETC. LARGER THAN 6 INCHES SHALL NOT BE PLACED IN SLABS, DECKS, BEAMS, JOISTS, COLUMNS, WALLS, ETC., UNLESS SPECIFICALLY DETAILED ON THE STRUCTURAL PLANS.
- ASTM SPECIFICATIONS NOTED SHALL BE THE LATEST REVISION
- THE CONTRACTOR SHALL INVESTIGATE THE SITE DURING CLEARING AND EARTHWORK OPERATIONS FOR FILLED EXCAVATIONS OR BURIED STRUCTURES SUCH AS CESSPOOLS, CISTERNS, FOUNDATIONS, ETC. IF ANY SUCH STRUCTURES ARE FOUND, THE ENGINEER OF RECORD SHALL BE NOTIFIED IMMEDIATELY.
- CONSTRUCTION MATERIALS SHALL BE SPREAD OUT IF PLACED ON FLOORS OR ROOF. LOAD SHALL NOT EXCEED THE DESIGN LIVE LOAD PER SQUARE FOOT. PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE STRUCTURE HAS NOT ATTAINED DESIGN STRENGTH.
- WHERE THE LONGEST HORIZONTAL CEILING DIMENSION IS EQUAL TO OR GREATER THAN 20'-0", IT IS RECOMMENDED THAT RESILIENT CHANNEL BE USED TO HELP LIMIT DRYWALL CRACKING.

DESIGN CRITERIA

	LIVE LOAD	DEAD LOAD
FLOOR LOAD	40 PSF	15 PSF
ROOF LOAD	20 PSF	22 PSF
ROOF SNOW LOAD	----	----
STAIR & EXIT LOAD	----	----
STORAGE LOAD	----	----
★ SEE FRAMING NOTES FOR SPECIAL LOADING CONDITIONS.		
BASIC WIND SPEED 100 MPH (LRFD), 78 MPH (ASD)		
WIND RISK CATEGORY II		
WIND EXPOSURE CATEGORY C		
INTERNAL PRESSURE COEFFICIENT ± 0.18		
SEISMIC RISK CATEGORY & IMPORTANCE II I _e = 1.0		
MAPPED SPECTRAL RESPONSE ACCELERATIONS S _{DS} = 0.498 & S ₀₁ = 0.162		
SPECTRAL RESPONSE COEFFICIENTS S _{DS} = 0.432 & S ₀₁ = 0.162		
SITE CLASS C		
LATERAL FORCE RESISTING SYSTEM LIGHT FRAME WALLS WITH SHEAR PANELS		R = 6.5
SEISMIC RESPONSE COEFFICIENT, C _s 0.086		
DESIGN BASE SHEAR C _s x DEAD WEIGHT(W)		
ANALYSIS PROCEDURE EQUIVALENT LATERAL FORCE		
SEISMIC DESIGN CATEGORY C		

FOUNDATION

- THIS IS TO CERTIFY THE FOUNDATION DEPICTED HEREIN HAS BEEN DESIGNED IN ACCORDANCE WITH RECOGNIZED ENGINEERING PRACTICE FOR CONDITIONS AS CLASSIFIED BY THE PROJECT GEOTECHNICAL REPORT.

CONSULTANT: DU PONT ENGINEERING, INC
PROJECT NO: 16-0414
DATED: SEPTEMBER 29, 2018
UPDATED: FEBRUARY 21, 2019
- FOOTINGS ARE DESIGNED BASED ON AN ALLOWABLE BEARING PRESSURE OF 2000 PSF PER SOIL REPORT.
- SOILS PREPARATION AND FOUNDATION CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS OF THE GEOTECHNICAL REPORT.
- SEE ARCHITECTURAL AND STRUCTURAL DRAWINGS FOR EXACT LOCATION OF BULKHEADS AND OPENINGS, ETC.
- THE CONTRACTOR SHALL PROVIDE FOR PROPER DE-WATERING OF EXCAVATIONS FROM SURFACE WATER, GROUND WATER, SEEPAGE, ETC. (FOOTINGS SHALL NOT BE PLACED UNDER WATER).
- FOOTINGS SHALL BE PLACED ACCORDING TO DEPTHS SHOWN ON THE STRUCTURAL PLANS. ALL ABANDONED FOOTINGS, UTILITIES, ETC. THAT INTERFERE WITH NEW CONSTRUCTION SHALL BE REMOVED.
- CONCRETE PLACEMENT SHALL BE IN ONE CONTINUOUS OPERATION UNLESS OTHERWISE SPECIFIED AND SLAB SURFACE SHALL BE CURED WITH HUNTS COMPOUND OR EQUAL.
- FOOTING BACKFILL AND UTILITY TRENCH BACKFILL WITHIN BUILDING AREA SHALL BE PER THE REQUIREMENTS OF THE GEOTECHNICAL REPORT. FLOODING WILL NOT BE PERMITTED.
- STOOPS, PORCHES, OR OTHER ATTACHMENTS SHALL BE CAST INDEPENDENT OF THE CONCRETE FOUNDATION SLAB, UNO.

FOUNDATION HARDWARE

- THICKEN SLAB AS REQUIRED FOR CONCRETE COVERAGE AT ANCHOR BOLTS PER ACI 318 WHERE OCCURS. THE CONCRETE CONTRACTOR SHALL VERIFY LOCATION OF ALL BOLTS, TIE-DOWNS, POST-ANCHORS, ETC. WITH THE ARCHITECTURAL PLANS PRIOR TO COMMENCING WORK AND BE RESPONSIBLE FOR SAME.
- UNO BOLT SILL PLATES TO THE FOUNDATIONS WITH MIN 1/2" NOMINAL DIA ANCHOR BOLT WITH PLATE WASHERS. BOLTS SHALL BE SPACED NOT MORE THAN 12" O.C. THERE SHALL BE A MIN OF (2) BOLTS PER PIECE. ONE BOLT SHALL BE LOCATED NOT MORE THAN 12" AND NOT LESS THAN 4" FROM EACH END, OR FROM EACH SIDE OF A NOTCH GREATER THAN 1/2 THE WIDTH OF THE PLATE. EMBEDD BOLTS AT LEAST 7" INTO REINFORCED MASONRY OR CONCRETE. SILL PLATE ANCHOR BOLTS MAY BE "WET SET".
- PROVIDE 3" X 3" X 0.229" PLATE WASHERS ON ALL ANCHOR BOLTS AT SHEAR WALLS. PLATE WASHERS SHALL EXTEND TO WITHIN 1/2" OF THE EDGE OF THE SILL PLATE ON THE SIDE(S) WITH SHEATHING. PROVIDE STANDARD OUT WASHERS UNDER BOLT HEADS AND NUTS WHEN SLOTTED PLATE WASHERS ARE USED. PROVIDE CUT OR SLOTTED WASHERS AGAINST WOOD AT ALL REMAINING WALLS.
- ALL 1/2" DIA. ANCHOR BOLTS MAY BE REPLACED WITH:
 - 1/2" DIA THREADED ROD EPOXY DOWELED TO FOUNDATION WITH SIMPSON SET-XP EPOXY (ICC REPORT ESR-2508) IN 5/8" DIA HOLE. PROVIDE A MIN. OF 4" EMBEDMENT AND 1 3/4" EDGE DISTANCE FROM ANY SLAB EDGE.
 - 1/2" DIA SIMPSON TITEN HD HIGH STRENGTH THREADED ANCHOR (ICC ESR-2713). PROVIDE A MIN. OF 4" EMBEDMENT AND 1 3/4" EDGE DISTANCE FROM ANY SLAB EDGE.
 - SIMPSON MASA MASAP MUDSILL ANCHORS (ICC ESR-2559). INSTALLATION OF THE MUDSILL ANCHOR SHALL BE PER MANUFACTURERS TYPICAL OR ALTERNATE INSTALLATION METHOD. DO NOT WET-SET THE MUDSILL ANCHOR. INSTALL WITH ONE LEG UP OR INSTALL OVER PLYWOOD OR OSB. FOLLOW ALL MANUFACTURERS SPECIFICATIONS AND RECOMMENDATIONS DURING INSTALLATION. DO NOT US WHEN ANCHOR SPACING IS < 9 INCHES.
- AT INTERIOR NON-BEARING AND NON-SHEARWALLS, 1/2" DIA ANCHOR BOLTS MAY BE REPLACED WITH MINIMUM 0.145" DIA X 2 7/8" POWDER DRIVEN FASTENERS AT A MAXIMUM SPACING OF 24" O.C. (HLTI ESR-2379 OR SIMPSON ESR-2138 OR EQUIVALENT)
- PROVIDE REINFORCING BAR FOR HOLDDOWNS PER DETAILS SHEET SD-1, UNO.
- HOLDOWNS SPECIFIED ON PLANS MAY BE POST INSTALLED (RETRO-FITTED) AS NOTED BELOW. DRILL COMPLETELY THRU THE FOOTING AND PROVIDE THREADED ROD WITH BEARING PLATE, WASHER AND NUT. BACKFILL ALL AROUND THE ROD, WASHER AND NUT TO PROVIDE A MINIMUM OF 3" COVER USING LEAN CONCRETE MIX. THREADED ROD AND BEARING PLATE SHALL BE PER THE TABLE PROVIDED. SEE RETROFIT DETAIL SHEET SD-1.1. THE USE OF POST INSTALLED ANCHORS UNLESS NOTED OTHERWISE, E.G. EXPANSION ANCHORS OR EPOXY ANCHORS, IS NOT ALLOWED WITHOUT PRIOR REVIEW AND AUTHORIZATION BY THE ENGINEER OF RECORD. CONTACT THE ENGINEER OF RECORD FOR REQUEST OF ALTERNATE ANCHORAGE SOLUTIONS.

REINFORCING STEEL

- REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-615 GRADE 60.
- WELDED REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-706 GRADE 60.
- ALL REINFORCING BAR BENDS SHALL BE MADE COLD.
- WELDED WIRE REINFORCEMENT (WWR) SHALL BE PER ASTM A1186 AND SHALL BE SUPPLIED IN SHEETS. WWR FIRM ROLLS SHALL NOT BE USED.
- MINIMUM LAP OF WELDED WIRE FABRIC SHALL BE 6 INCHES OR ONE AND ONE HALF SQUARES, WHICHEVER IS GREATER.
- ALL BARS SHALL BE MARKED SO THEIR IDENTIFICATION CAN BE MADE WHEN THE FINAL IN-PLACE INSPECTION IS MADE.
- REBAR SPLICES ARE TO BE CLASS "B" (UNO), MAINTAIN 2 BAR DIA CLEAR SPACE BETWEEN ADJACENT SPLICES.
- REINFORCING SPLICES SHALL BE MADE ONLY WHERE INDICATED ON THE DRAWINGS.
- DOWELS BETWEEN FOOTINGS AND WALLS OR COLUMNS SHALL BE THE SAME GRADE, SIZE AND SPACING OR NUMBER AS THE VERTICAL REINFORCING, RESPECTIVELY, UNO.

REBAR SIZE	3	4	5	6	7	8	9	10	11
MINIMUM LAP LENGTH (INCHES)	22	29	36	43	68	78	88	98	107
STD HOOK LENGTH (INCHES)	4 1/2	6	7 1/2	9	10 1/2	12	13 1/2	15 1/2	16 1/2



CONCRETE

- ALL PHASES OF WORK PERTAINING TO THE CONCRETE CONSTRUCTION SHALL CONFORM TO THE 'BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE' (ACI 318 LATEST ADOPTED EDITION), WITH MODIFICATIONS AS NOTED IN THE DRAWINGS AND SPECIFICATIONS.
- REINFORCED CONCRETE DESIGN IS BY THE 'ULTIMATE STRENGTH DESIGN METHOD'.
- SCHEDULE OF STRUCTURAL CONCRETE 28-DAY STRENGTHS AND TYPES:

LOCATION IN STRUCTURE	STRENGTH	PSI TYPE
SLABS ON GRADE	4500 PSI	HARD ROCK
FOOTINGS	4500 PSI	HARD ROCK

DESIGN BASED ON 2500 PSI, 28-DAY STRENGTH, THEREFORE SPECIAL INSPECTION IS NOT REQUIRED.
- CONCRETE MIX DESIGN SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR APPROVAL WITH THE FOLLOWING REQUIREMENTS:
 - COMPRESSIVE STRENGTH AT AGE 28 DAYS AS SPECIFIED ABOVE.
 - LARGE AGGREGATE-HARDROCK: 3/4" MAXIMUM SIZE CONFORMING TO ASTM C-33.
 - CEMENT: ASTM C-150, TYPE V PORTLAND CEMENT.
 - MAXIMUM SLUMP: 5 INCHES.
 - NO ADMIXTURES, EXCEPT FOR ENTRAINED AIR, AND AS APPROVED BY THE ENGINEER.
 - WATER/CEMENT RATIO SHALL BE AS FOLLOWS:
 - fc = 4500 PSI.....w/c = 0.45
 - fc = 4000 PSI.....w/c = 0.5
 - fc < 4000 PSI.....w/c = PER MIX DESIGN
 - FLY ASH: ASTM C618
 - SLAG: ASTM C989
 - SILICA FUME: ASTM C1240
 - LIGHTWEIGHT AGGREGATE: ASTM C330
 - AIR ENTRAINING ADMIXTURE: ASTM C60
 - WATER REDUCERS: ASTM C494, TYPE A OR F
- CONCRETE MIXING OPERATIONS, ETC, SHALL CONFORM TO ASTM C-94.
- PLACEMENT OF CONCRETE SHALL CONFORM TO ACI STANDARD 814 AND PROJECT SPECIFICATIONS.
- CLEAR COVERAGE OF CONCRETE OVER OUTER REINFORCING BARS SHALL BE AS FOLLOWS:
 - CONCRETE POURED DIRECTLY AGAINST EARTH: 3 INCHES CLEAR
 - STRUCTURAL SLABS: 3/4 INCHES CLEAR, TOP AND BOTTOM (2" TOP; 3/4" BOTTOM IN CORROSIVE ENVIRONMENTS)
 - FORMED CONCRETE WITH EARTH BACKFILL: 2 INCHES CLEAR
- ALL REINFORCING BARS, HOLD DOWN BOLTS AND STRAPS, AND OTHER CONCRETE INSERTS SHALL BE WELL SECURED IN POSITION PRIOR TO PLACING CONCRETE.
- PROVIDE SLEEVES FOR PLUMBING AND ELECTRICAL OPENINGS IN CONCRETE BEFORE PLACING. DO NOT CUT ANY REINFORCING WHICH MAY CONFLICT. CORING IN CONCRETE IS NOT PERMITTED EXCEPT AS SHOWN. NOTIFY THE STRUCTURAL ENGINEER IN ADVANCE OF CONDITIONS NOT SHOWN ON THE DRAWINGS.

- CONDUIT OR PIPE SIZE (O.D.) SHALL NOT EXCEED 30% OF SLAB THICKNESS AND SHALL BE PLACED BETWEEN THE TOP AND BOTTOM REINFORCING, UNLESS SPECIFICALLY DETAILED OTHERWISE. CONCENTRATIONS OF CONDUITS OR PIPES SHALL BE AVOIDED EXCEPT WHERE DETAILED OPENINGS ARE PROVIDED.
- MODULUS OF ELASTICITY OF CONCRETE, WHEN TESTED IN ACCORDANCE WITH ASTM C-460, SHALL BE AT LEAST THE VALUE GIVEN BY THE EQUATIONS IN SECTION 8.5.1 OF ACI 318 FOR THE SPECIFIED 28-DAY STRENGTH.
- SEE FOUNDATION DETAILS FOR REINFORCEMENT REQUIRED AT CORNERS AND INTERSECTIONS OF CONCRETE WALLS, CONVENTIONAL FOOTINGS AND GRADE BEAMS.

WOOD

- FRAMING LUMBER, UNO:
 - 2X AND 4X TO BE DOUGLAS FIR LARCH (DFL) NO. 2 GRADE. SEE FRAMING PLANS AND NOTES FOR WALL STUD REQUIREMENTS.
 - 6X TO BE DOUGLAS FIR LARCH NO. 1 GRADE.
 - ALL LUMBER SHALL HAVE A MOISTURE CONTENT OF LESS THAN 19%.
- BOLT HOLES SHALL BE 1/16" (MAXIMUM) LARGER THAN THE BOLT SIZE. RE-TIGHTEN ALL NUTS PRIOR TO CLOSING IN.
- ALL SILLS OR PLATES RESTING ON CONCRETE OR MASONRY SHALL BE PRESSURE-TREATED DOUGLAS FIR USING BORON BASED PRESERVATIVES OR LSL TREATED WITH ZINC BORATE.
- DO NOT NOTCH JOISTS, RAFTERS, OR BEAMS, EXCEPT WHERE SHOWN IN DETAILS. OBTAIN ENGINEERS APPROVAL FOR ANY HOLES OR NOTCHES NOT DETAILED.
- WHERE A POST OCCURS AT AN UPPER LEVEL, ADD THE SAME POST DIRECTLY BELOW IT ON THE LOWER LEVELS AND IN BETWEEN FLOOR SHEATHING AND LOWER LEVEL WALL PLATES.
- FACE NAIL EACH PLY OF MULTIPLE 2X POSTS WITH 16D SINKERS AT 6" O.C.
- PROVIDE MULTIPLE 2X POST AT ALL GIRDER TRUSS AND BEAM BEARING LOCATIONS, WIDTH TO MATCH BEAM OR TRUSS, MIN. (2) 2X UNO.
- CONNECTION HARDWARE SHALL BE SIMPSON OR EQUAL AND MUST BE I.C.C. APPROVED.
- FOR CONNECTIONS NOT DETAILED, PROVIDE FASTENERS PER TABLE 2304.9.1 OF THE LATEST ADOPTED EDITION OF THE INTERNATIONAL BUILDING CODE.
- DO NOT NOTCH TOP PLATES OR STUDS EXCEPT AS SHOWN IN DETAILS. OBTAIN ENGINEERS APPROVAL FOR ANY HOLES OR NOTCHES NOT DETAILED.
- NON-BEARING WALLS SHALL HAVE STUDS SPACED AT 24" O.C. (MAX). REFER TO ARCHITECTURAL DRAWINGS FOR SIZE. TOP PLATES SHALL BE SUCH THAT A 1/2" GAP BETWEEN THE TOP OF THE PLATES AND THE BOTTOM OF THE TRUSSES AND/OR BLOCKING PANELS EXISTS AFTER THE ROOF IS LOADED.

# OF 16d SINKERS	1	2	3	4	5	6	7	8	9	10	11	12
# OF 0.131 X 3 1/4" GUN NAILS	2	3	4	5	6	7	8	9	11	12	13	14

SPACING OF 16d SINKERS	2" OC	4" OC	6" OC	8" OC	10" OC	12" OC
SPACING OF 0.131 X 3 1/4" GUN NAILS	11/2" OC	3 1/2" OC	5" OC	7" OC	8 1/2" OC	10 1/2" OC

HARDWARE	NAILING REQUIRED
LTP4 AT 32" OC UNO	(8) 8d x 1 1/2" INTO TRUSS (4) 8d x 1 1/2" INTO PLATE

HARDWARE	NAILING REQUIRED
LTP4 AT 32" OC UNO	(8) 8d x 1 1/2" INTO TRUSS (4) 8d x 1 1/2" INTO PLATE

- NOTES:
- SEE DETAIL 1/SD-3 FOR STANDARD NAILING REQUIREMENTS
 - SEE FRAMING PLANS FOR NON-STANDARD UPLIFT HARDWARE

MANUFACTURED BEAMS

- GLUE LAMINATED BEAMS (GLB)
 - GLB SHALL BE 24F-V4, (CONTINUOUS AND CANTILEVERED GLB SHALL BE 24F-V8) AND HAVE THE FOLLOWING MINIMUM PROPERTIES: FB=2400 PSI, FV=240 PSI
FC (PERPENDICULAR) = 650 PSI
E = 1,800,000 PSI
 - ALL BEAMS SHALL BE FABRICATED USING EXTERIOR GLUE. FABRICATION AND HANDLING PER LATEST ATC AND WCCA STANDARDS. BEAMS TO BEAR GRADE STAMP AND ATC STAMP AND CERTIFICATE.
 - MOISTURE CONTENT SHALL BE LIMITED TO A MAXIMUM OF 12%.
 - ALL GLB SHALL HAVE STANDARD CAMBER, UNO, ON PLANS.
- LAMINATED STRAND LUMBER (1.3E OR 1.5E LSL)
 - LSL BEAMS SHALL HAVE I.C.C. APPROVAL AND HAVE THE FOLLOWING MINIMUM PROPERTIES:
 - LSL (1.3E) - E = 1,300,000 PSI, FB = 1700 PSI, FV = 400 PSI
FC (PERPENDICULAR) = 680 PSI, FC (PARALLEL) = 1400 PSI
 - LSL (1.5E) - E = 1,500,000 PSI, FB = 2250 PSI, FV = 400 PSI
FC (PERPENDICULAR) = 750 PSI, FC (PARALLEL) = 1950 PSI
 - ALL MULTI-PLY LSL MEMBERS SPECIFIED ON PLANS MAY BE REPLACED WITH SOLID MEMBERS OF EQUAL OR GREATER PROPERTIES WITH EQUAL OR GREATER WIDTH AND DEPTH WITHOUT FURTHER REVIEW.
- LAMINATED VENEER LUMBER (LVL)
 - LVL BEAMS SHALL HAVE I.C.C. APPROVAL AND HAVE THE FOLLOWING MINIMUM PROPERTIES:
 - LVL (1.7E) - E = 1,700,000 PSI, FB = 2650 PSI, FV = 285 PSI
FC (PERPENDICULAR) = 750 PSI, FC (PARALLEL) = 3000 PSI
 - LVL (1.9E) - E = 1,900,000 PSI, FB = 2600 PSI, FV = 285 PSI
FC (PERPENDICULAR) = 750 PSI, FC (PARALLEL) = 2510 PSI
 - LVL (2.0E) - E = 2,000,000 PSI, FB = 2800 PSI, FV = 285 PSI
FC (PERPENDICULAR) = 750 PSI, FC (PARALLEL) = 3000 PSI
 - MULTIPLE-PLY LVL BEAMS SHALL BE NAILED TOGETHER AS FOLLOWS:
 - PROVIDE (2) ROWS OF 16D SINKERS AT 12" O.C.
FOR BEAMS < 11 7/8" DEEP
 - PROVIDE (3) ROWS OF 16D SINKERS AT 12" O.C.
FOR BEAMS > 11 7/8" DEEP.
 - ALL MULTI-PLY LVL MEMBERS SPECIFIED ON PLANS MAY BE REPLACED WITH SOLID MEMBERS OF EQUAL OR GREATER PROPERTIES WITH EQUAL OR GREATER WIDTH AND DEPTH WITHOUT FURTHER REVIEW.
- PARALLEL STRAND LUMBER (PSL)
 - PSL BEAMS SHALL HAVE I.C.C. APPROVAL AND HAVE THE FOLLOWING MINIMUM PROPERTIES:
E = 2,000,000 PSI, FB = 2900 PSI, FV = 290 PSI
FC (PERPENDICULAR) = 750 PSI, FC (PARALLEL) = 2900 PSI

PREFABRICATED WOOD TRUSSES

- PREFABRICATED WOOD ROOF TRUSSES SHALL BE AS DESIGNED BY THE TRUSS MANUFACTURER (INCLUDING BRIDGING SIZE AND SPACING) UNO. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS, ERECTION DRAWINGS, AND DESIGN CALCULATIONS, SEALED BY AN ENGINEER, REGISTERED IN THE STATE OF THE GOVERNING JURISDICTION, FOR REVIEW PRIOR TO MANUFACTURE. CALCULATIONS AND SHOP DRAWINGS SHALL SHOW ANY SPECIAL DETAILS REQUIRED AT BEARING POINTS. ALL CONNECTORS SHALL HAVE CURRENT I.C.C. APPROVAL.
- TRUSS MANUFACTURER TO DESIGN TRUSSES FOR LATERAL LOAD (LAT. = XXXX) IN POUNDS, AS SHOWN ON PLANS.
- UNLESS OTHERWISE NOTED, TRUSSES TO BE DESIGNED FOR LOADS INDICATED IN THE DESIGN CRITERIA AND AS FOLLOWS:
 - TOP CHORD DEAD LOAD = XXX + ADDITIONAL 5 PSF AT OVERFRAMING.
 - BOTTOM CHORD DEAD LOAD = XXX.
 - WIND LOAD: WHEN CALCULATING NET UPLIFT REACTIONS, USE MAXIMUM RESISTING DEAD LOAD = XXX PSF ON TOP CHORD AND XXX PSF ON BOTTOM CHORD
- TRUSS MANUFACTURER TO DESIGN TRUSSES TO SUPPORT MECHANICAL EQUIPMENT AS REQUIRED. ADDITIONAL TRUSSES MAY BE SUPPLIED AS REQUIRED.
- ALL TRUSS TO TRUSS CONNECTORS PER TRUSS MANUFACTURER.
- WHERE POST OCCURS ABOVE A MANUFACTURED TRUSS, A VERTICAL WEB SHALL BE PROVIDED UNDER THE POST. THE WEB SECTION AREA SHALL BE EQUAL TO OR LARGER THAN POST SECTION AREA. MULTIPLE 2X4S MAY BE USED FOR THE VERTICAL WEB.
- THE TOP CHORD OF ALL TRUSSES SHALL HAVE A SPECIES WITH SPECIFIC GRAVITY EQUAL TO OR GREATER THAN 0.42.
- TRUSS MANUFACTURER SHALL LIMIT TOTAL LOAD DEFLECTIONS TO LESS THAN L/240 AND LIVE LOAD DEFLECTIONS TO LESS THAN L/360. DEFLECTION SHALL BE LIMITED SO AS NOT TO CREATE A BEARING CONDITION AT NON-BEARING WALLS. REFER ALSO TO NOTE 11 OF THE WOOD SECTION.
- CONNECTION OF MANUFACTURED TRUSSES FOR UPLIFT SHALL BE PER THE TABLES ON SHEET S1.1.
- TRUSSES SHALL BE DESIGNED TO SUPPORT A 250 POUND CONCENTRATED LOAD AT ANY LOCATION ALONG THE BOTTOM CHORD.

STANDARD TRUSSES ⁽²⁾		
REACTIONS TO THE BEARING WALL OR BEAM BELOW:		
TRUSS TYPE & TOTAL LENGTH	HARDWARE REQUIRED	NAILING REQUIRED
JACK TRUSSES ≤ 10'-0"	NONE REQUIRED	UPLIFT IS RESISTED BY EXISTING NAILED CONNECTION OF TRUSS TO PLATE ⁽¹⁾
HIP/COMMON TRUSSES ≤ 30'-0" L ≤ 50'-0"	NONE REQUIRED	UPLIFT IS RESISTED BY EXISTING NAILED CONNECTION OF TRUSS TO PLATE ⁽¹⁾
HIP/COMMON TRUSS 30'-0" ≤ L ≤ 50'-0"	H1 OR H2.5	(8) 8d x 1 1/2" INTO TRUSS (4) 8d x 1 1/2" INTO PLATE
ALL HIP/COMMON DRAG TRUSSES L ≤ 50'-0"	H1 OR H2.5	(8) 8d x 1 1/2" INTO TRUSS (4) 8d x 1 1/2" INTO PLATE
HIP/COM. GIRDER RFT SETBACK L ≤ 30'-0"	H10 OR (2) H2.5	(8) 8d x 1 1/2" INTO TRUSS (8) 8d x 1 1/2" INTO PLATE
HIP/COM. GIRDER RFT SETBACK L ≤ 40'-0"	HTS20	(12) 10d x 1 1/2" INTO TRUSS (12) 10d x 1 1/2" INTO PLATE & STUD BLW
HIP/COM. GIRDER RFT SETBACK L ≤ 40'-0"	(2) HTS20	(12) 10d x 1 1/2" INTO TRUSS (12) 10d x 1 1/2" INTO PLATE & STUD BLW
ALL OTHER NON DRAG GIRDER TR L ≤ 40'-0"	H1 OR H2.5	(8) 8d x 1 1/2" INTO TRUSS (4) 8d x 1 1/2" INTO PLATE
ALL OTHER GIRDER TRUSSES L ≤ 50'-0"	H10 OR (2) H2.5	(8) 8d x 1 1/2" INTO TRUSS (8) 8d x 1 1/2" INTO PLATE

AT TRUSSES WHERE THE HARDWARE ABOVE CANNOT BE INSTALLED, PROVIDE AN HTS20 STRAP

GABLE END WALL TRUSSES	
HARDWARE	NAILING REQUIRED
LTP4 AT 32" OC UNO	(8) 8d x 1 1/2" INTO TRUSS (4) 8d x 1 1/2" INTO PLATE



- NOTES:
- SEE DETAIL 1/SD-3 FOR STANDARD NAILING REQUIREMENTS
 - SEE FRAMING PLANS FOR NON-STANDARD UPLIFT HARDWARE

SHEET INDEX	
SHT #	SHEET NAME
S1	GENERAL NOTES
S1.1	SCHEDULES AND NOTES
S2	LOWER FOUNDATION PLAN
S2.1	MAIN FOUNDATION & FLOOR FRAMING PLAN
S2.2	MAIN FOUNDATION & FLOOR FRAMING PLAN
S3	ROOF FRAMING PLAN
S3.1	ROOF FRAMING PLAN
S4	LOWER SHEAR WALL PLAN
S4.1	MAIN SHEAR WALL PLAN
SD-1	STRUCTURAL DETAILS
SD-1.1	STRUCTURAL DETAILS
SD-2	STRUCTURAL DETAILS
SD-2.1	STRUCTURAL DETAILS
SD-3	STRUCTURAL DETAILS
SD-4	STRUCTURAL DETAILS
SD-5	STRUCTURAL DETAILS
SD-6	STRUCTURAL DETAILS
WSW1	SIMPSON STRONG-WALL DETAILS
WSW2	SIMPSON STRONG-WALL DETAILS

SHEARWALL SCHEDULE ^(2, 5, 8, 11, 12, 13)					
SHEARWALL ^(7, 17)			ONE SIDED SHEARWALL TWO SIDED SHEARWALL ⁽⁶⁾		SEISMIC WIND
MARK	MATERIAL ^(4, 14)	NAILING	UPPER FLOOR SILL PL CONN ^(1, 18)	ANCHOR BOLTS ⁽⁵⁾ (UNO ON FOUNDATION PLAN)	ALLOWABLE SHEAR
P1	3/8" APA SHEATHING ⁽¹⁵⁾	8dN AT 6" OC EDGES, 12" FIELD ⁽¹⁶⁾	16dS AT 4" OC (STG'D) UNO	1/2" DIA X 10" AT 32" OC	260#/FT 365#/FT
P2	3/8" APA SHEATHING ⁽¹⁵⁾	8dN AT 4" OC EDGES, 12" FIELD ⁽¹⁶⁾	16dS AT 3" OC, (STG'D) UNO	1/2" DIA X 10" AT 24" OC	350#/FT 532#/FT
P3	3/8" APA SHEATHING ^(9, 15)	8dN AT 3" OC EDGES, 12" FIELD ⁽¹⁶⁾	1/4x6 SCREWS AT 4" OC (STG'D), UNO	1/2" DIA X 10" AT 16" OC	490#/FT 685#/FT
P4	3/8" APA SHEATHING ^(9, 15)	8dN AT 2" OC EDGES, 12" FIELD ⁽¹⁶⁾	1/4x6 SCREWS AT 4" OC (STG'D), UNO	1/2" DIA X 10" AT 12" OC	600#/FT 895#/FT
P5	15/32" APA SHEATHING ⁽¹⁰⁾	10dN AT 2" OC EDGES, 12" FIELD ⁽¹⁶⁾	1/4x6 SCREWS AT 3" OC (STG'D), UNO	1/2" DIA X 10" AT 9" OC	770#/FT 1078#/FT
SCHEDULE NOTES:					
(1) SEE DETAIL 7/SD-2 FOR ADDT'L INFO AT UPPER FLOOR SILL PLATE CONNECTION FOR MULTI-STORY PLANS ONLY. DOES NOT APPLY TO SINGLE STORY PLANS. SEE PLAN FOR SILL PLATE AND SHEAR CONNECTIONS AT EXTERIOR WALLS.					
(2) OPENINGS IN SHEARWALL SHEATHING SHALL NOT EXCEED 8 INCHES IN ANY DIRECTION FOR A SINGLE OPENING OR THE SUM OF ANY TWO OR MORE OPENINGS ON COMMON OR OVERLAPPING VERTICAL OR HORIZONTAL LINES. OPENINGS NOT GREATER THAN 8 INCHES DO NOT REQUIRE BLOCKING AROUND THE PENETRATION. CONTACT THE ENGINEER OF RECORD FOR REQUIREMENTS AT OPENINGS NOT OTHERWISE DETAILED.					
(3) MINIMUM (2) 1/2" DIA ANCHORS PER SHEAR WALL. SEE FOUNDATION HARDWARE NOTES, NOTE 2 ON THE GENERAL NOTES SHEET, S1. ALL ANCHOR BOLTS SHALL HAVE 3" x 3" x 0.229" PLATE WASHERS.					
(4) APA RATED (STRUCTURAL II) PLYWOOD OR OSB.					
(5) SEE DETAIL 11/SD-2 WHERE WALL FRAMING STEPS OR PERPENDICULAR WALL INTERSECTS SHEAR WALL.					
(6) FOR SHEAR PANELS ON TWO SIDES OF WALL, USE ONE-HALF THE SPACING GIVEN IN THE SCHEDULE FOR SILL PLATE CONNECTION AND ANCHOR BOLT SPACING, UNO.					
(7) DOUBLE SIDED SHEARWALLS SHALL HAVE VERTICAL PANEL JOINTS OFFSET TO FALL ON DIFFERENT STUDS OR USE SINGLE 3" NOMINAL STUDS (MIN) AT JOINTS. AT THE ENDS OF THE SHEARWALL, 4X NOMINAL MEMBERS ARE REQUIRED. NAILS ON EACH SIDE SHALL BE STAGGERED.					
(8) ALL SHEARWALLS REQUIRE DOUBLE 2X TOP PLATES, U.N.O. AT NON-BEARING SHEAR WALLS, SHORTEN STUDS 1/4 INCH TO PROVIDE DEFLECTION CLEARANCE.					
(9) P2, P3 AND P4 SHEARWALLS SHALL REQUIRE THE FOLLOWING: A. STAGGER NAILING ALONG PLYWOOD JOINTS AND SILL PLATES. B. SINGLE 3" NOMINAL MEMBERS AT ALL FRAMING MEMBERS RECEIVING EDGE NAILING FROM ABUTTING PANELS. 3" NOMINAL MEMBERS AT SINGLE SIDED SHEARWALL MAY BE CONSTRUCTED W/ (2) 2X MEMBERS FASTENED TOGETHER W/ (2) ROWS OF 16d SINKERS AT 4" OC.					
(10) P5 SHEARWALLS SHALL REQUIRE SINGLE 3" NOMINAL MEMBERS AT ALL FRAMING MEMBERS RECEIVING EDGE NAILING FROM ABUTTING PANELS (MIN), STAGGER JOINT AND SILL PLATE NAILING.					
(11) ALL SHEARWALL LENGTHS NOTED ON PLAN ARE MINIMUM REQUIRED AND MAY BE INCREASED WITHOUT REVIEW.					
(12) SHEATHING MAY BE PLACED ON EITHER FACE OF DESIGNATED WALL, UNO.					
(13) ALLOWABLE SHEAR CAPACITIES ARE IN ACCORDANCE WITH AF&PA SDPWS TABLE 4.3A WITH APPLICABLE OMEGA FACTORS INCLUDED.					
(14) APA SHEATHING AND GYPSUM SHEATHING MAY BE INSTALLED WITH THE LONG OR SHORT DIRECTION PERPENDICULAR TO THE FRAMING. WHERE APA SHEATHING IS INSTALLED WITH THE SHORT DIRECTION PERPENDICULAR TO THE FRAMING, THE FRAMING MUST BE 16" ON CENTER (MAX). WHERE GYPSUM SHEATHING IS INSTALLED WITH THE SHORT DIRECTION PERPENDICULAR TO THE FRAMING ALL PANEL EDGES MUST BE BLOCKED AND NAILED.					
(15) 3/8" SHEATHING MAY BE REPLACED WITH 7/16" OR 15/32" SHEATHING WITHOUT ADDITIONAL REVIEW.					
(16) ALL VERTICAL AND HORIZONTAL PANEL EDGES TO BE BLOCKED AND NAILED.					
(17) STUDS SHALL BE 24" OC (MAX). FOR 3/8" AND 7/16" SHEATHING, FIELD NAILING SHALL BE REDUCED TO 6" OC WHERE STUD SPACING IS GREATER THAN 16" OC.					
(18) SILL PLATE CONNECTORS SHALL BE PER SHEAR TRANSFER DETAIL SPECIFIED ON PLANS.					

HOLDOWN/STRAP SCHEDULE ^(1, 2)		
HD/STRAP	EMBED AT FND AND / OR ANCHOR BOLT	CONN TO (2) 2X STUD, UNO ^(3, 6, 10)
CS16	N/A	EXTEND STRAP 16" MIN. EA. END W/ (13) 8dN TO (2) 2X STUD ABOVE AND BELOW FLOOR FRAMING
(2) CS16	N/A	EXTEND STRAP 16" MIN. EA. END W/ (13) 8dN TO (2) 2X STUD ABOVE AND BELOW FLOOR FRAMING
CMSTC16	N/A	EXTEND STRAP 25" MIN. EA. END W/ (26) 16d SINKERS TO (2) 2X STUD ABOVE AND BELOW FLOOR FRAMING
CMST14	N/A	EXTEND STRAP 32" MIN. EA. END W/ (33) 16dN TO (3) 2X STUD ABOVE AND BELOW FLOOR FRAMING
CMST12	N/A	EXTEND STRAP 40" MIN. EA. END W/ (42) 16dN TO (3) 2X STUD ABOVE AND BELOW FLOOR FRAMING
LSTHD8 ^(4, 11)	8" EMBED	(20) 16d SINKERS
STHD10 ^(4, 11)	10" EMBED	(24) 16d SINKERS
STHD14 ^(4, 11)	14" EMBED	(30) 16d SINKERS
HTT5	SSTB24 W/ 21" EMBED ⁽¹²⁾	(26) 16dN X 2 1/2" NAILS
HDU2	SSTB24 W/ 21" EMBED ⁽¹²⁾	(6) SDS 1/4 X 2 1/2 SCREWS W/ MIN (2) 2X POSTS
HDU4	SSTB24 W/ 21" EMBED ⁽¹²⁾	(10) SDS 1/4 X 2 1/2 SCREWS W/ MIN (2) 2X POSTS
HDU5	SSTB24 W/ 21" EMBED ⁽¹²⁾	(14) SDS 1/4 X 2 1/2 SCREWS W/ MIN (2) 2X POSTS
HDU8	SSTB34 W/ 29" EMBED ⁽¹³⁾	(20) SDS 1/4 X 2 1/2 SCREWS W/ MIN (3) 2X POSTS
HDU11	1" DIA AB W/ 9" MIN EMBED W/ MIN 28" SQ x 14" DEEP FTG ⁽⁹⁾	(30) SDS 1/4 X 2 1/2 SCREWS W/ MIN 4x8 POST ⁽⁹⁾
HDU14	1" DIA AB W/ 10" MIN EMBED W/ MIN 30" SQ X 15" DEEP FTG ⁽⁷⁾	(36) SDS 1/4 X 2 1/2 SCREWS W/ MIN 4x8 POST ⁽⁹⁾
SCHEDULE NOTES:		
(1) HD/STRAP SHALL BE SIMPSON OR EQUAL W/ ICC APPROVAL. ALL SUBSTITUTES SHALL BE REVIEWED BY THE ENGINEER OF RECORD BEFORE INSTALLATION.		
(2) FIXED-LENGTH STRAPS SHALL BE INSTALLED WITH AN EQUAL LENGTH OVERLAPPING CONNECTED MEMBERS AND AN EQUAL NUMBER OF FASTENERS IN EACH MEMBER.		
(3) STITCH NAIL EACH STUD AT MULTIPLE 2x STUDS TOGETHER WITH 16d SINKERS AT: 4" OC FOR P3 AND P4 SHEAR WALLS 6" OC FOR ALL OTHER SHEAR WALLS		
(4) FOR CONCRETE SPALLS LESS THAN 4", THERE IS NO LOAD REDUCTION AND NO FURTHER REVIEW BY EOR IS REQUIRED.		
(5) SEE DETAIL 4/SD-2 FOR ADDL CRITERIA AT UPPER FLOOR STRAPS (WHERE OCCURS).		
(6) EDGE NAIL SHTG TO EA MEMBER OF MULTIPLE POST, OFFSET 1/2 SPACING BTWN MEMBERS.		
(7) ASTM F1554-55 BOLT W/ HEAVY SQUARE NUT OR 1/4 X 1 3/4 X 1 3/4 PLATE WASHER REQUIRED FOR FULL LOAD. REDUCE ALLOWABLE LOAD TO 13180 LBS FOR ASTM GRADE 36 BOLT. MINIMUM EMBEDMENT IS FROM TOP OF FOOTING.		
(8) ASTM GRADE 36 BOLT W/ SQUARE OR HEAVY HEX HEAD OR NUT REQUIRED. MINIMUM EMBEDMENT IS FROM TOP OF FOOTING.		
(9) PROVIDE 6x8 POST AT 2x6 WALLS, MULTIPLE STUDS NOT ALLOWED.		
(10) END POST TO BE FULL HEIGHT MEMBERS, UNO.		
(11) STRAPS MAY BE PLACED ON EITHER FACE OF DESIGNATED WALL AND ARE NOT REQUIRED TO OCCUR ON SAME FACE AS SHEATHING, UNO.		
(12) AT GARAGE STEMWALL LOCATIONS USE SSTBL.		
(13) WHEN SLAB AND FOOTINGS ARE PLACED AS A MONO-POUR, SSTB28 WITH 25" EMBEDMENT MAY BE SUBSTITUTED FOR THE SSTB34 SPECIFIED.		

FOUNDATION NOTES:	
A.	AT INTERIOR BEARING WALLS, WITHOUT DEEPEEN FOOTINGS, USE 1/2" DIA TITEN HD HIGH STRENGTH SCREW ANCHORS IN LIEU OF ANCHOR BOLTS.
B.	SEE DETAIL 1/SD-1 FOR PERIMETER FOOTING EMBEDMENT DEPTH.
C.	VERIFY ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS.

FRAMING NOTES:			
1. ALL EXTERIOR WALLS AND INTERIOR BEARING AND SHEAR WALLS TO BE MIN 2x6 AT 16" O.C. DFL STUD GRADE, UNO. SEE FRAMING PLANS FOR NON-TYPICAL STUD SIZE AND SPACING.			
2. TRIMMER / KING STUD SCHEDULE, UNO.			
	OPENING SPAN (L)	TRIMMERS	KING STUDS
2x4 WALLS	L < 6'-0"	1	1
	6'-0" ≤ L < 10'-0"	2	2
	10'-0" ≤ L < 18'-0"	2	3
2x6 WALLS	L < 8'-0"	1	1
	8'-0" ≤ L < 12'-0"	2	2
	12'-0" ≤ L < 20'-0"	2	3
3.  BLOCKED DIAPHRAGM - SEE STRUCTURAL GENERAL NOTES SHEET S1.			
4. FOR TYPICAL OVERFILL FRAMING WHERE REQUIRED BY TRUSS SHOP DRAWINGS, SEE DETAILS 4/SD-3 OR 5/SD-3.			
5.  INTERIOR BEARING WALLS			
6. BEAM AND HEADER SIZES INDICATED ON THIS PLAN ARE MINIMUM. LARGER SIZES OR HIGHER GRADE LUMBER MAY BE SUBSTITUTED.			
7. TOP PLATE SPLICES PER DETAIL 3/SD-2, UNO.			
8. SEE DETAIL 8/SD-2 FOR ADDITIONAL FRAMING REQUIREMENTS.			

LEDGER & HANGER SCHEDULE:				
UNLESS OTHERWISE NOTED 2X LEDGERS WHERE DETAILED SHALL BE AS FOLLOWS:				
ROOF LOAD	FLOOR LOAD	4x MEMBER	TRUSS	
			SPAN (L)	SPACING (MAX)
			LEDGER AND NAILING ^(1, 2, 6, 10, 11)	
			MIN HANGER, UNO ^(3, 4, 5, 11)	
FLOOR LOAD	2x MEMBER	2x MEMBER	L ≤ 8'-0"	16" O.C.
				24" O.C.
			L ≤ 16'-0"	24" O.C.
				24" O.C.
FLOOR LOAD	2x MEMBER	2x MEMBER	L ≤ 24'-0"	24" O.C.
				24" O.C.
			L ≤ 10'-0"	16" O.C.
				24" O.C.
DECK LOAD	2x MEMBER	2x MEMBER	L ≤ 10'-0"	16" O.C.
				24" O.C.
			L ≤ 15'-0"	24" O.C.
				24" O.C.

- SCHEDULE NOTES:
- TWO COLUMNS OF FASTENERS REQUIRE MIN SUPPORTING MEMBER RECEIVING FASTENERS OF 3" OR (2)2X IN WIDTH (ENDS OF 4x2 OR DOUBLE TRUSSES ARE ACCEPTABLE). SPACE FASTENERS MIN 1" APART IN EACH DIRECTION.
 - SPACING SHOWN EQUALS SPACING OF FRAMING MEMBERS RECEIVING FASTENERS.
 - HANGERS LISTED IN ORDER ARE BY SIMPSON STRONG-TIE AND USP, RESPECTIVELY.
 - LISTED HANGERS ARE MINIMUM HANGERS REQUIRED WHERE NOT OTHERWISE NOTED ON THE STRUCTURAL DRAWINGS.
 - SPACING SHOWN FOR HANGERS IS SPACING OF THE FRAMING MEMBER SUPPORTED BY THE HANGER.
 - LEDGER MATERIAL SHALL BE DFL #2 OR BETTER UNO. LEDGER AT DECK SHALL BE PRESSURE-PRESERVATIVE TREATED OR NATURALLY DURABLE WOOD.
 - PROVIDE THA218 (MIN) HANGER FOR ROOF TRUSS TO BEAM CONNECTIONS FOR ALL BEAM DEPTHS GREATER THAN 10 INCHES.
 - PROVIDE THA418 (MIN) HANGER FOR FLOOR TRUSS TO BEAM CONNECTIONS FOR ALL BEAM DEPTHS GREATER THAN 10 INCHES.
 - PROVIDE THA422 (MIN) HANGER FOR FLOOR TRUSS TO BEAM CONNECTONS FOR ALL BEAM DEPTHS GREATER THAN 18 INCHES.
 - ALL SIMPSON SCREWS NOTED SHALL BE STRONG DRIVE SDS SCREWS.
 - HANGERS AND FASTENERS WITH EXTERIOR EXPOSURE SHALL BE STAINLESS STEEL, UNLESS NOTED OTHERWISE.

L. R. NELSON CONSULTING ENGINEERS, INC.


6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com


CIVIL
FORENSICS
PLANNING
STRUCTURAL
SURVEY

ASSURED DEVELOPMENT, INC.

ATHENS LOT 2

2 IDAHO WAY, HENDERSON, NV





LOWER FOUNDATION PLAN

1/4"=1'-0"

FOOTING AND PIER SCHEDULE

OPTIONAL CONTROL JOINT

BASE PER FDN

NOTE 4

C.G.

D

CENTER FTG BELOW WALL ABOVE

L x W

3" CLR

NOTE 5

REINFORCEMENT

F.F.

L x W

3" CLR

EXTERIOR ISOLATED FOOTING

INTERIOR ISOLATED FOOTING

F.G. = FINISHED GRADE

C.G. = COMPACTED SUB-GRADE

	MARK	SIZE L x W x D	REINFORCEMENT	REMARKS
PIER	P1	NOTE 1	(4) #4 DOWELS W/ 6" HOOK (1) #3 TIE	NOTE 2
	F1	L x W x 1'-0"	#4 AT 12" O.C. EA WAY BOTT	NOTE 6
FOOTING	F2	2'-0" SQ x 1'-0"	(2) #4 EA WAY, BOTT	
	F2.5	2'-6" SQ x 1'-0"	(3) #4 EA WAY, BOTT	
	F3	3'-0" SQ x 1'-0"	(3) #4 EA WAY, BOTT	
	F4	4'-0" SQ x 1'-0"	(5) #4 EA WAY, BOTT	

FOOTING AND PIER NOTES:

1. SIZE TO MATCH ARCH'L BOXED COLUMN (SEE DETAIL 11/SD-1)

2. TOP OF PIER=FINISHED FLOOR

3. TIES SHALL HAVE 1 1/2" COVER & BE LOCATED 2" FROM TOP OF PIER

4. EMBEDMENT BELOW COMPACTED SUB-GRADE PER DETAIL 11/SD-1

5. SEE DETAIL 4/SD-1 FOR MINIMUM EMBEDMENT DEPTH FROM TOP OF SLAB OR LOWEST ADJACENT COMPACTED SUBGRADE

6. SIZE TO MATCH BOX COLUMN + 6" EA. SIDE

JOB NO: 1939-002-191
DESIGNED BY: KAB
DRAWN BY: ACM
ISSUED FOR:
CONSTRUCTION DOCUMENTS
DATE: 12-08-19
SHEET TITLE:
FOUNDATION PLAN
REVISIONS:

L. R. NELSON CONSULTING ENGINEERS, INC.


6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com

CIVIL
FORENSICS
PLANNING
STRUCTURAL
SURVEY

ASSURED DEVELOPMENT, INC.


ATHENS LOT 2

2 IDAHO WAY, HENDERSON, NV



01-07-20

SEE SHEET S1.1 FOR FOUNDATION
NOTES AND HOLDOWN SCHEDULE



MAIN FOUNDATION & FLOOR FRAMING PLAN


1/4" = 1'-0"


SEE SHEET S1.1 FOR FOUNDATION
NOTES AND HOLDOWN SCHEDULE

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com

CIVIL
FORENSICS
PLANNING
STRUCTURAL
SURVEY

ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV






MAIN FOUNDATION & FLOOR FRAMING PLAN
MFR TRUSS OPTION
1/4"=1'-0"


SEE SHEET S1.1 FOR FOUNDATION
NOTES AND HOLDOWN SCHEDULE

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com
• CIVIL
• FORENSICS
• PLANNING
• STRUCTURAL
• SURVEY

ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV



S2.2



ROOF FRAMING PLAN

1/4"=1'-0"

SEE SHEET S1.1 FOR FRAMING NOTES

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
www.lrneng.com


CIVIL
FORENSICS
PLANNING
STRUCTURAL
SURVEY

ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV

KENT A. BARBER
Exp. 12-31-20
CIVIL
STRUCTURAL
No. 017213
NVLIN 30

S3





LOWER SHEAR WALL PLAN

1/4"=1'-0"

SEE SHEET S1.1 FOR SHEAR WALL
AND HOLDOWN SCHEDULES


JOB NO: 1939-002-191
DESIGNED BY: KAB
DRAWN BY: ACM
ISSUED FOR:
CONSTRUCTION DOCUMENTS
DATE: 12-08-19
SHEET TITLE:
SHEAR WALL PLAN
REVISIONS:

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com
• CIVIL
• FORENSICS
• PLANNING
• STRUCTURAL
• SURVEY

ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV

KENT A. BARBER
Exp. 12-31-20
No. 017213
01-07-20

S4



MAIN SHEAR WALL PLAN

1/4" = 1'-0"


SEE SHEET S1.1 FOR SHEAR WALL
AND HOLDOWN SCHEDULES

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com


- CIVIL
- FORENSICS
- PLANNING
- STRUCTURAL
- SURVEY

ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV


KENT A. BARBER
Exp. 12-31-20
CIVIL
STRUCTURAL
No. 017213
01-07-20




SECTION "A-A"




13




9 HOLDOWN W/ ANCHOR BOLT (TYPICAL) NTS



10 REINFORCING AT HOLDOWNS NTS




11 CONCRETE PIER AND FOOTING NTS




NOTES:
1. THIS DETAIL IS FOR BOX COL SILL PL. (SEE FND PLAN FOR LOCATIONS)
2. PROVIDE MAS ANCHORS AT PL LENGTHS LESS THAN 8'

12 BOX COLUMN SILL PLATE NTS




NOTE 1:
GREATER DEPTH AS REQUIRED FOR HOLDOWNS AND HOLDOWN ANCHOR BOLTS.

5 STEP IN SLAB NTS




6 TYP SLAB JOINTS NTS




SEE DTL 3/- FOR INFORMATION NOT SHOWN

7 CURB BETWEEN GARAGE DOORS NTS




SEE DTL 1/- FOR INFORMATION NOT SHOWN

8 STRAP HOLDOWN NTS




NOTE 1:
BOTTOM OF FTG SHALL BE 15\"/>

1 EDGE OF FOUNDATION NTS




SEE DTL 1/- FOR INFO NOT SHOWN

2 EDGE OF FOUNDATION (GARAGE) N.T.S.



SEE DTL 1/- FOR INFO NOT SHOWN

3 EDGE OF FOUNDATION (CURB) NTS



NOTE 1:
GREATER DEPTH AS REQUIRED FOR HOLDOWNS AND HOLDOWN ANCHOR BOLTS.


4 INTERIOR CONTINUOUS FTG NTS

JOB NO: 1939-002-191
DESIGNED BY: KAB
DRAWN BY: ACM
ISSUED FOR:
CONSTRUCTION DOCUMENTS
DATE: 12-08-19
SHEET TITLE:
STRUCTURAL DETAILS
REVISIONS:


L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
www.lrneng.com
• CIVIL
• FORENSICS
• PLANNING
• STRUCTURAL
• SURVEY

ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV


KENT A. BARBER
Exp. 12-31-20
No. 017213
01-07-20




4 RESTRAINED WALL NTS




5 TYP CONCRETE WALL CORNER NTS



1 NTS



2 NTS




3 NTS







JOB NO: 1939-002-191
DESIGNED BY: KAB
DRAWN BY: ACM
ISSUED FOR:
CONSTRUCTION DOCUMENTS
DATE: 12-08-19
SHEET TITLE:
STRUCTURAL DETAILS
REVISIONS:

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com
• CIVIL
• FORENSICS
• PLANNING
• STRUCTURAL
• SURVEY


ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV




SD-1.1




1 TYP SHEAR TRANSFER DILS




2X4 PLATE W/ DRILLED HOLES




2X4 PLATE W/ NOTCHES




2X6 PLATE W/ DRILLED HOLES




2X6 PLATE W/ NOTCHES




2X4 PLATE W/ DRILLED HOLES



2X4 PLATE W/ NOTCHES



2X6 PLATE W/ DRILLED HOLES




2X6 PLATE W/ NOTCHES

* HARDWARE MANUFACTURED BY HARDY FRAMES SEE MFR PRODUCT CATALOG


3 ALLOWABLE HOLES AND NOTCHES IN PLATES

INTERIOR WALLS (BEARING AND NON-BEARING)


NTS



2X4 STUD W/ NOTCHES



2X6 STUD W/ NOTCHES



2X4 STUD W/ DRILLED HOLES 2X6 STUD W/ DRILLED HOLES

4 ALLOWABLE HOLES AND NOTCHES IN STUDS


INTERIOR NON-BEARING WALLS

NTS


1 ALLOWABLE HOLES AND NOTCHES IN PLATES

EXTERIOR WALLS AND INTERIOR SHEAR WALLS


NTS



2X4 STUD W/ NOTCHES



2X6 STUD W/ NOTCHES



2X4 STUD W/ DRILLED HOLES 2X6 STUD W/ DRILLED HOLES

2 ALLOWABLE HOLES AND NOTCHES IN STUDS

EXTERIOR WALLS, INTERIOR SHEAR WALLS AND INTERIOR BEARING WALLS

NTS





JOB NO: 1939-002-191
DESIGNED BY: KAB
DRAWN BY: ACM
ISSUED FOR:
CONSTRUCTION DOCUMENTS
DATE: 12-08-19
SHEET TITLE:
STRUCTURAL DETAILS
REVISIONS:

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com
• CIVIL
• FORENSICS
• PLANNING
• STRUCTURAL
• SURVEY





ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV

KENT A. BARBER
Exp. 12-31-20
No. 017213
01-07-20





SD-2.1







15 TYP INTERIOR FLOOR JOIST BEARING



11



7 STAIR FRAMING



4 CANTILEVERED FLOOR JOIST


JOB NO: 1939-002-191
DESIGNED BY: KAB
DRAWN BY: ACM
ISSUED FOR:
CONSTRUCTION DOCUMENTS
DATE: 12-08-19
SHEET TITLE:
STRUCTURAL DETAILS
REVISIONS:

L. R. NELSON CONSULTING ENGINEERS, INC.
6765 West Russell Rd Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com
• CIVIL
• FORENSICS
• PLANNING
• STRUCTURAL
• SURVEY


ASSURED DEVELOPMENT, INC.
ATHENS LOT 2
2 IDAHO WAY, HENDERSON, NV

KENT A. BARBER
Exp. 12-31-20
No. 017213
01-07-20


SD-3




9 TYPICAL VALLEY BEAM DETAIL NTS




5 NTS




1 RAFTER TO TOP PLATE NTS




10 ROOF TO WALL CONNECTION NTS




6 NTS




2 RAFTER TO TOP PLATE NTS




11 NTS




7 NTS



3 OUTRIGGER FRAMING DETAIL NTS



8 NTS




4 RAFTER AT WALL NTS

JOB NO: 1939-002-191
 DESIGNED BY: KAB
 DRAWN BY: ACM
 ISSUED FOR:
 CONSTRUCTION DOCUMENTS
 DATE: 12-08-19
 SHEET TITLE:
 STRUCTURAL DETAILS
 REVISIONS:


L. R. NELSON CONSULTING ENGINEERS, INC.
 6765 West Russell Rd Suite 200
 Las Vegas, Nevada 89118
 (702) 798-7978
 (702) 451-2296 FAX
 www.lrneng.com
 • CIVIL
 • FORENSICS
 • PLANNING
 • STRUCTURAL
 • SURVEY

ASSURED DEVELOPMENT, INC.
 ATHENS LOT 2
 2 IDAHO WAY, HENDERSON, NV


KENT A. BARBER
 Exp. 12-31-20
 CIVIL/STRUCTURAL
 No. 017213
 01-07-20




11 BRACING AT NON-BRG WALLS




12 RIDGE BLOCKING




13 LOW ROOF TO WALL




14 EXTERIOR WALL BRACING




7 PONY WALL




8 PONY WALL




9 TRUSS W/ DEEP HEEL AT BEARING




10 TRUSS TO GIRDER




PLAN




4 OVERFILL FRAMING



5 OVERFILL FRAMING




6 STEP IN ROOF



NOTES:

- NOTES:**
- A. EVERY 4TH BLOCK MAY BE DELETED FOR EAVE VENT INSTALLATION
 - B. SEE DTL 4/- FOR HEEL DEPTH GREATER THAN 11 /14"
 - C. REFER TO ARCH'L DRAWINGS FOR HEEL HEIGHT

1 EAVE CONDITION




NOTE 1

NOTE 1:
VERTICAL UNBRACED HEIGHT OF GABLE END WALL TRUSS MAY NOT EXCEED 4'-0".
ADD ADDITIONAL SECONDARY BRACES AS REQ'D TO MAINTAIN THE MAXIMUM UNBRACED HEIGHT.
EXCEPTION: WHERE TOTAL GABLE END WALL TRUSS HEIGHT IS LESS THAN 6'-0" THE SECONDARY BRACE
MAY BE OMITTED

NOTE 2

NOTE 2:
AT GABLE END WALL SCISSOR TRUSS WITH HEIGHT IS LESS THAN 6'-0", PROVIDE 3 BAYS OF BLOCKING
PANELS. PER DETAIL 2/SD-2. AT 6'-0" OC SPACING IN LIEU OF 2X DIAGONAL BRACES.


② GABLE END WALL TRUSS



3 2X FLAT OUTRIGGER


12

8 DECK LEDGER




13

9



14


10




15

11


8 DECK LEDGER



9




10




11


5 FLOOR TRUSS TO BEAM



6 FLOOR TR TO BEAM




7 STAIR FRAMING




7 STAIR FRAMING


1 FLR TR PERP. TO EXT WALL





2 FLR TR PARALLEL TO EXT WALL




3




4 CANTILEVERED FLOOR TR



WSW PANEL MODEL	MODEL NO.	DIAMETER	LENGTH	I_b
WSW12 AND WSW18	WSW-AB7/8x24	7/8"	24"	20"
	WSW-AB7/8x24HS	7/8"	24"	20"
	WSW-AB7/8x30	7/8"	30"	26"
	WSW-AB7/8x30HS	7/8"	30"	26"
	WSW-AB7/8x36HS	7/8"	36"	32"
WSW24	WSW-AB1x24	1"	24"	20"
	WSW-AB1x24HS	1"	24"	20"
	WSW-AB1x30	1"	30"	26"
	WSW-AB1x30HS	1"	30"	26"
	WSW-AB1x36HS	1"	36"	32"



WSW PANEL MODEL	MODEL NO.	DIAMETER	LENGTH	l _b
WSW12 AND WSW18	WSW-HSR7/8x24KT	7/8"	24"	22"
	WSW-HSR7/8x36KT	7/8"	36"	34"
WSW24	WSW-HSR1x24KT	1"	24"	22"
	WSW-HSR1x36KT	1"	36"	34"



STRONG-WALL® WSW ANCHORAGE - TYPICAL SECTIONS

1

WSW ANCHOR BOLTS


3

WSW ANCHOR BOLT EXTENSION

4

WSW ANCHOR BOLT TEMPLATES

6



FOUNDATION PLAN VIEW


WSW ANCHORAGE SOLUTIONS FOR 2500 PSI CONCRETE									
DESIGN CRITERIA	CONCRETE CONDITION	ANCHOR STRENGTH	WSW-AB/7 ANCHOR BOLT			WSW-AB/1 ANCHOR BOLT			
			ASD ALLOWABLE TENSION (lb.)	W (in.)	d ₆ (in.)	ASD ALLOWABLE TENSION (lb.)	W (in.)	d ₆ (in.)	
SEISMIC	CRACKED	STANDARD	11,900	27	9	16,100	33	11	
			13,100	29	10	17,100	35	12	
		HIGH STRENGTH	24,900	43	15	33,000	51	17	
			27,100	46	16	35,300	54	18	
	UNCRAKED	STANDARD	12,500	24	8	15,700	28	10	
			13,100	25	9	17,100	30	10	
		HIGH STRENGTH	25,300	38	13	32,300	44	15	
			27,100	40	14	35,300	47	16	
	WIND	CRACKED	STANDARD	5,100	14	6	6,200	16	6
				8,700	20	7	11,400	24	8
13,100				27	9	17,100	32	11	
HIGH STRENGTH			15,900	30	10	21,100	36	12	
			18,400	33	11	27,300	42	14	
			23,100	38	13	31,800	46	16	
UNCRAKED		STANDARD	27,100	42	14	35,300	50	17	
			5,000	12	6	6,400	14	6	
			9,300	18	6	12,500	22	8	
		HIGH STRENGTH	13,100	23	8	17,100	28	10	
15,200	25		9	21,900	32	11			
19,900	30		10	26,400	36	12			
			24,000	34	12	31,500	40	14	
			27,100	37	13	35,300	43	15	

NOTES:


- ANCHORAGE DESIGNS CONFORM TO ACI 318-11 APPENDIX D AND ACI 318-14 WITH NO SUPPLEMENTARY REINFORCEMENT FOR CRACKED OR UNCRACKED CONCRETE AS NOTED.
- ANCHOR STRENGTH INDICATES REQUIRED GRADE OF WSW-A8 ANCHOR BOLT. STANDARD (ASTM F1554 GRADE 36) OR HIGH STRENGTH (HS) (ASTM A449).
- SEISMIC INDICATES SEISMIC DESIGN CATEGORY C - F. DETACHED 1 AND 2 FAMILY DWELLINGS IN SDC C MAY USE WIND ANCHORAGE.
- ANCHOR STRENGTH INDICATES CONFORM TO ACI 318-11 SECTION D.3.4.3 AND ANCHOR BOLT EMBEDMENT 17.2.3.4.3.
- WIND INCLUDES SEISMIC DESIGN CATEGORY A AND B AND DETACHED 1 AND 2 FAMILY DWELLINGS IN SDC C.
- FOUNDATION DIMENSIONS ARE FOR ANCHORAGE ONLY. FOUNDATION DESIGN (SIZE AND REINFORCEMENT) BY OTHERS. THE REGISTERED DESIGN PROFESSIONAL MAY SPECIFY ALTERNATE EMBEDMENT, FOOTING SIZE OR ANCHOR BOLT.
- REFER TO 11WSW1 FOR ϕ_c .

WSW ANCHORAGE SOLUTIONS FOR 3000 PSI CONCRETE									
DESIGN CRITERIA	CONCRETE CONDITION	ANCHOR STRENGTH	WSW-AB7/8 ANCHOR BOLT			WSW-AB1 ANCHOR BOLT			
			ASD ALLOWABLE TENSION (lb.)	W (in.)	d ₆ (in.)	ASD ALLOWABLE TENSION (lb.)	W (in.)	d ₆ (in.)	
SEISMIC	CRACKED	STANDARD	12,300	26	9	16,000	31	11	
			13,100	28	10	17,100	33	11	
		HIGH STRENGTH	25,200	41	14	32,700	48	16	
			27,100	43	15	35,300	51	17	
	UNCRAKED	STANDARD	12,000	22	8	16,300	27	9	
			13,100	24	8	17,100	28	10	
		HIGH STRENGTH	25,300	36	12	32,700	42	14	
			27,100	38	13	35,300	44	15	
	WIND	CRACKED	STANDARD	5,000	13	6	5,600	14	6
				8,800	19	7	10,200	21	7
13,100				25	9	17,100	30	10	
HIGH STRENGTH			15,700	28	10	20,100	33	11	
			19,200	32	11	25,300	38	13	
			23,200	36	12	32,300	44	15	
UNCRAKED		STANDARD	27,100	40	14	35,300	47	16	
			5,500	12	6	6,200	13	6	
			8,500	16	6	12,800	21	7	
		HIGH STRENGTH	13,100	22	8	17,100	26	9	
16,600	25		9	21,800	30	10			
19,700	28		10	25,200	33	11			
24,000	32		11	31,700	38	13			
			27,100	35	12	35,300	41	14	


WSW ANCHORAGE SOLUTIONS FOR 4500 PSI CONCRETE									
DESIGN CRITERIA	CONCRETE CONDITION	ANCHOR STRENGTH	WSW-AB/7/8 ANCHOR BOLT			WSW-AB1 ANCHOR BOLT			
			ASD ALLOWABLE TENSION (lb.)	W (in.)	d _B (in.)	ASD ALLOWABLE TENSION (lb.)	W (in.)	d _B (in.)	
SEISMIC	CRACKED	STANDARD	12,600	23	8	16,000	27	9	
			13,100	24	8	17,100	29	10	
		HIGH STRENGTH	24,800	36	12	32,100	42	14	
			27,100	38	13	35,300	45	15	
	UNCRAKED	STANDARD	12,700	20	7	15,700	23	8	
			13,100	21	7	17,100	25	9	
		HIGH STRENGTH	24,600	31	11	32,500	37	13	
			27,100	34	12	35,300	39	13	
	WIND	CRACKED	STANDARD	5,400	12	6	6,800	14	6
				8,300	16	6	11,600	20	7
13,100				22	8	17,100	26	9	
15,300				24	8	21,400	30	10	
HIGH STRENGTH			19,300	28	10	25,800	34	12	
			23,600	32	11	31,000	38	13	
			27,100	36	12	35,300	42	14	
			6,800	12	6	6,800	12	6	
UNCRAKED		STANDARD	9,400	15	6	12,400	18	6	
			13,100	19	7	17,100	23	8	
	HIGH STRENGTH	16,800	22	8	21,600	26	9		
		20,300	25	9	26,700	30	10		
			24,100	28	10	32,200	34	12	
			27,100	31	11	35,300	36	12	



HAIRPIN SHEAR REINFORCEMENT




TIE SHEAR REINFORCEMENT



HAIRPIN INSTALLATION

(GARAGE CURB SHOWN. OTHER FOOTING TYPES SIMILAR.)



SECTION A-A

STRONG-WALL® WOOD SHEARWALL SHEAR ANCHORAGE							
MODEL	L _t OR L _h (in.)	SEISMIC ³		WIND ⁴			
		SHEAR REINFORCEMENT	MINIMUM CURB/ STEMWALL WIDTH (in.)	SHEAR REINFORCEMENT	MINIMUM CURB/ STEMWALL WIDTH (in.)	ASD ALLOWABLE SHEAR LOAD, V (lb.) ⁶	
						UNCRAKED	CRACKED
WSW12	10½	(1) #3 HAIRPIN	8 ⁵	SEE NOTE 6	6	1,035	740
WSW18	15	(1) #3 HAIRPIN	8 ⁵	(1) #3 HAIRPIN	6	HAIRPIN REINFORCEMENT ACHIEVES MAXIMUM ALLOWABLE SHEAR LOAD OF THE WSW	
WSW24	19	(2) #3 HAIRPINS	8 ⁵	(1) #3 HAIRPIN	6		

NOTES:

1. SHEAR ANCHORAGE DESIGNS CONFORM TO ACI 318-11 AND ACI 318-14 AND ASSUME MINIMUM 2,500 PSI CONCRETE.
2. SHEAR REINFORCEMENT IS NOT REQUIRED FOR INTERIOR FOUNDATION APPLICATIONS (PANEL INSTALLED AWAY FROM EDGE OF CONCRETE), OR BRACKET WALL PANEL APPLICATIONS.
3. SEISMIC INDICATES SEISMIC DESIGN CATEGORY C THROUGH F. DETACHED 1 AND 2 FAMILY DWELLINGS IN SDC C MAY USE WIND ANCHORAGE SOLUTIONS.
4. WIND INCLUDES SEISMIC DESIGN CATEGORY A AND B AND DETACHED 1 AND 2 FAMILY DWELLINGS IN SDC C.
5. NOTED: MINIMUM CURB/STEWALL WIDTH IS 6 INCHES WHEN STANDARD STRENGTH ANCHOR BOLT IS USED.
6. #1 TO #4 FOR WSW12 WHEN PANEL DESIGN SHEAR FORCE EXCEEDS TABULATED ANCHORAGE ALLOWABLE SHEAR LOAD.
7. #4 GRADE 50 SHEAR REINFORCEMENT MAY BE SUBSTITUTED FOR WSW12 SHEAR ANCHORAGE SOLUTIONS.

STRONG-WALL® WOOD SHEARWALL TENSION ANCHORAGE SCHEDULE 2,500, 3,000 AND 4,500 PSI

2

STRONG-WALL® WSW SHEAR ANCHORAGE SCHEDULE AND DETAILS

5

MODEL NO.	W (in.)	H (in.)	ANCHOR BOLTS		TOTAL WALL WEIGHT (lb.)
			QUANTITY	DIA. (in.)	
WSW12x7	12	78	2	7/8	100
WSW18x7	18	78	2	7/8	145
WSW12x7.5	12	85 1/2	2	7/8	110
WSW18x7.5	18	85 1/2	2	7/8	155
WSW12x8	12	93 1/4	2	7/8	115
WSW18x8	18	93 1/4	2	7/8	165
WSW24x8	24	93 1/4	2	1	225
WSW12x9	12	105 1/4	2	7/8	130
WSW18x9	18	105 1/4	2	7/8	185
WSW24x9	24	105 1/4	2	1	245
WSW12x10	12	117 1/4	2	7/8	140
WSW18x10	18	117 1/4	2	7/8	205
WSW24x10	24	117 1/4	2	1	270
WSW12x11	12	129 1/4	2	7/8	150
WSW18x11	18	129 1/4	2	7/8	220
WSW24x11	24	129 1/4	2	1	295
WSW12x12	12	141 1/4	2	7/8	165
WSW18x12	18	141 1/4	2	7/8	240
WSW24x12	24	141 1/4	2	1	320
WSW18x13	18	153 1/4	2	7/8	255
WSW24x13	24	153 1/4	2	1	345
WSW24x14	24	168	2	1	375
WSW24x16	24	192	2	1	425
WSW18x20	18	240	2	7/8	385
WSW24x20	24	240	2	1	520

PLACE STRONG-WALL® WOOD SHEARWALL OVER THE ANCHOR BOLTS AND SECURE WITH WASHER AND HEX NUTS (PROVIDED). SNUG TIGHT FIT REQUIRED; DO NOT USE AN IMPACT WRENCH.

- USE 1½" WRENCH FOR ¾" NUT
- USE 1½" WRENCH FOR 1" NUT

$\frac{7}{8}$ " MAXIMUM WOOD SHIM. FOR SHIMS GREATER THAN $\frac{1}{4}$ ". SEE 9/WSW2.

TOP PLATES

ALIGN WSW-TOW NOTCHES WITH BOTTOM OF TOP PLATES

ATTACH WSW-TOW PLATES (PROVIDED) TO FRAMING AND WSW PANEL BOTH SIDES USING 10d x 2 $\frac{1}{2}$ " NAILS MIN. FOR ALTERNATE CONNECTION SEE 7/WSW2.

DFL, SP OR SCL WOOD FURRING BLOCK (REQUIRED FOR 5 $\frac{1}{2}$ "-6 $\frac{1}{2}$ " MEMBERS)

3" MIN.

2" MIN.

2" MIN.

3" MIN.

SDS $\frac{1}{2}$ " x 3 $\frac{1}{2}$ "

SECTION 4x FRAMING

STRONG-WALL® WOOD SHEARWALL

SECTION 6x FRAMING

LTP4 SPACING BY OTHERS

REGISTERED DESIGN PROFESSIONAL IS PERMITTED TO MODIFY DETAILS FOR SPECIFIC CONDITIONS.

INSTALL SDS 1/4" x 6" SCREWS (MIN.) FROM THE TOP SIDE OF THE PLATES PER QTY. AND SPACING REQUIREMENTS DETAILED IN 8WSW2.

4x SHIM BLOCK

FULL-HEIGHT ADJACENT FRAMING BY OTHERS

SEE 6 & 7/WSW2 FOR TOP CONNECTION

4x SHIM BLOCK

STRONG-WALL® WOOD SHEARWALL

4" TO 12" SHIM BLOCK

1" TO 4" SHIM BLOCK

REGISTERED DESIGN PROFESSIONAL
SHALL DESIGN AND DETAIL FOR:

1. SHEAR TRANSFER
2. OUT-OF-PLANE LOADING EFFECTS
3. INCREASED OVERTURNING MOMENTS DUE TO ADDITIONAL LOADS

FOR 8" TO 12" BLOCK DEPTHS:
ATTACH SIMPSON STRONG-TIE
EDGE OF WSW PANEL (EACH S

SHIM BLOCK HEIGHTS GREATER THAN 8" AND UP TO 10"

- 8 NAILS INTO BLOCK
- 8 NAILS INTO WSW PANEL

SHIM BLOCK HEIGHTS GREATER THAN 10" AND UP TO 12"

- 10 NAILS INTO BLOCK
- 10 NAILS INTO WSW PANEL

SEE 6 & 7/WSW2 F
TOP CONNECTION

[illegible]

—STRONG-WALL®
WOOD SHEARWALL

TOP OF WALL HEIGHT ADJUSTMENTS



WSW DESIGNED TO PROVIDE $\frac{1}{8}$ " GAP BETWEEN
LSL AT BASE OF WSW AND CONCRETE. ENSURE
CONCRETE IS LEVEL AND SMOOTH BENEATH
PANEL. GRIND OR FILL AS NECESSARY

PLACE STRONG-WALL® WOOD SHEARWALL OVER THE ANCHOR BOLTS AND SECURE WITH WASHER AND HEX NUTS (PROVIDED). SNUG TIGHT FIT REQUIRED; DO NOT USE AN IMPACT WRENCH.

- USE 1 $\frac{1}{16}$ " WRENCH FOR $\frac{7}{8}$ " NUT
- USE 1 $\frac{1}{2}$ " WRENCH FOR 1" NUT

STRONG-WALL® WOOD SHEARWALL HEIGHT TO INCLUDE THE DEPTH OF THE FLOOR SYSTEM AND SHALL BE INSTALLED DIRECTLY ON THE FOUNDATION. SPECIFY PANEL HEIGHT FROM TOP OF FOUNDATION TO UNDERSIDE OF TOP PLATES OR BEAM

SECTION

REGISTERED DESIGN PROFESSIONAL
IS PERMITTED TO MODIFY DETAILS
FOR SPECIFIC CONDITIONS.



TRAINING



HOLES FOR WSW24X7 PANEL ONLY

- MAX. OF ONE 4 $\frac{1}{8}$ " x 6" HOLE
- 8" FROM TOP OF PANEL, MIN.

HOLES FOR WSW24X7 PANEL ONLY

- MAX. OF ONE 4 $\frac{1}{8}$ " x 6" HOLE
- 8" FROM TOP OF PANEL, MIN.

TRIM ZONE AND ALLOWABLE HOLES



WHEN WSW-PS STRAPS OMITTED,
ALLOWABLE SHEAR VALUES FOR
STANDARD PANEL APPLY.

GARAGE HEADER ROUGH OPENING HEIGHT		
MODEL NO.	H CURB	ROUGH OPENING HEIGHT
WSW12x7	5½"	6'-11½"
WSW18x7	6"	7'-0"
WSW24x7		
WSW12x7.5	0"	7'-1½"
WSW18x7.5		
WSW24x7.5		
WSW12x8	5½"	8'-2¾"
WSW18x8	6"	8'-3¾"
WSW24x8		

NOTES:

1. IF REQUIRED ROUGH OPENING HEIGHT EXCEEDS TABLE VALUE, SPECIFY NEXT TALLER PANEL AND TRIM AS NECESSARY. THE STRONG-WALL® WOOD SHEARWALL MAY BE TRIMMED TO A MINIMUM HEIGHT OF 74½".
2. FURRING DOWN GARAGE HEADER MAY BE REQUIRED FOR CORRECT ROUGH OPENING HEIGHT.

FOR GARAGE WALL OPTION 2, REGISTERED DESIGN PROFESSIONAL SHALL DESIGN AND DETAIL FOR :

1. SHEAR TRANSFER
2. OUT-OF-PLANE LOADING EFFECT
3. INCREASED OVERTURNING AND DRIFT DUE TO ADDITIONAL HEIGHT

8

11

REVISIONS

L. R. NELSON CONSULTING ENGINEERS, INC.

6765 West Russell Rd. Suite 200
Las Vegas, Nevada 89118
(702) 798-7978
(702) 451-2296 FAX
www.lrneng.com

- CIVIL
- FORENSICS
- PLANNING
- STRUCTURAL
- SURVEY

ASSURED DEVELOPMENT, INC.

ATHENS LOT 2

2 IDAHO WAY, HENDERSON, NV

Professional Engineer - State of Nevada
 KENT A. BARBER
 Exp. 12-31-20
 CIVIL / STRUCTURAL
 No. 017213

01-07-

WSW2